

From:

Kent Handyman Service

Website : www.kenthandymanservice.co.uk

Email : info@kenthandymanservice.co.uk

Tel : 07544 792604

Company Number 10134263

Waste Carrier License - CBDU208239

Estimate Number	KHS-0514
Estimate Date	18/10/2018
Valid Until	17/11/2018
Total	£12,348.00

To:

Mary X8R

45a Whitehall Road

Ramsgate

CT12 6DE

01843446643

admin@x8r.co.uk

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Office 1 - 3.7m x 6.1m Stud all walls with 2x2 timber Supply 100mm rock wool to fill new created cavity's in walls and ceiling. Supply and install pink back fire proof plaster boards for walls and ceiling All materials and labour included All area to be covered approx 92 sqm	£4,508.00	0%	£4,508.00
1	Office 2 - 3.3m x 4.7m Stud all walls and ceiling with 2x2 timber Supply 100mm rock wool to fill new created cavity's in walls and ceiling. Supply and install pink back fire proof plaster boards for walls and ceiling All materials and labour included All area to be covered approx 70 sqm	£3,430.00	0%	£3,430.00

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Office 3 - 3.6m x 6.1m Remove 8x4 sheets of cladding and stud work on all 4 walls Stud all walls and ceiling with 2x2 timber Supply 100mm rock wool to fill new created cavity's in walls and ceiling. Supply and install pink back fire proof plaster boards for walls and ceiling All materials and labour included All area to be covered approx 90 sqm	£4,410.00	0.00%	£4,410.00

Sub Total	£12,348.00
VAT	£0.00
Total	£12,348.00

Please visit our website for our Terms and conditions